Date	Estimate No.

Estimate To

Description				Quantity	Rate	Amount
Electrical works as detailed below :	Plot 1 - Rear of 5 Seafield Avenue					
Living Room	Double plug sockets			5		
	Ceiling pendant light			2		
	Light switch	(1 gang / 1way)		1		
	TV point		**(see Note 1)**	1		
Hall	Double plug sockets			1		
	Ceiling pendant light			2		
	Outside porch light	(surface / weatherproof)		1		
	Light switch	(3 gang / 2way)		1		
	Light switch	(1 gang / 2way)		1		
	Smoke dectector	(interlinkled)		1		
WC	Ceiling pendant light			1		
	Light switch	(1 gang / 1way)		1		
Study	Double plug sockets			3		
	Ceiling pendant light			1		
	Light switch	(1 gang / 1way)		1		
Kitchen	Double plug sockets			5		
	Recessed ceiling light			6		
	Light switch	(3 gang / 2way)		1		
	Cooker / Hob supply			1		
	Fitted appliance supply		**(see Note 2)**	4		
	TV point		**(see Note 1)**	1		
Breakfast Area	Double plug sockets			2		
	Ceiling pendant light			1		
Dinning Room	Double plug sockets			3		
	Ceiling pendant light			1		
	Light switch	(1 gang / 2way)		1		
Utility	Double plug sockets			3		
	Ceiling pendant light			1		
	Light switch	(1 gang / 2way)		2		
Garage	Ceiling pendant light			1		
	Light switch	(1 gang / 2way)		1		

Landing	Double plug sockets				1		
	Ceiling pendant light				2		
	Light switch	(2 gang / 3way)			1		
	Light switch	(1 gang / 3way)			1		
	Smoke dectector	(interlinkled)			2		
Bathroom	Ceiling light	(surface / bathroom rated)			1		
	Light switch	(1 gang / 1way)			1		
	Shaver point				1		
Master Bedroom	Double plug sockets				4		
	Ceiling pendant light				1		
	Light switch	(1 gang / 1way)			1		
	TV point			**(see Note 1)**	1		
	BT phone extension point				1		
Master En Suite	Ceiling light	(surface / bathroom rated)			1		
	Light switch	(1 gang / 1way)			1		
	Shaver point				1		
Master Dressing Room	Double plug sockets				1		
	Ceiling pendant light				1		
	Light switch	(1 gang / 1way)			1		
Bedroom 2	Double plug sockets				4		
	Ceiling pendant light				1		
	Light switch	(1 gang / 1way)			1		
Bed 2 En Suite	Ceiling light	(surface / bathroom rated)			1		
	Light switch	(1 gang / 1way)			1		
	Shaver point				1		
Bed 2 Dressing Room	Double plug sockets				1		
	Ceiling pendant light				1		
	Light switch	(1 gang / 1way)			1		
Bedroom 3	Double plug sockets				3		
	Ceiling pendant light				1		
	Light switch	(1 gang / 1way)			1		
Bedroom 4	Double plug sockets				3		
	Ceiling pendant light				1		
	Light switch	(1 gang / 1way)			1		
Bedroom 5	Double plug sockets				3		
	Ceiling pendant light				1		
	Light switch	(1 gang / 1way)			1		
Consumer Unit	+ earth bonds				1		
Central Heating	Boiler supply			**(see Note 3)**	1		
	Programmer			**(see Note 3)**	1		
	Immersion			**(see Note 3)**	1		
	Room stat			**(see Note 3)**	1		
	Wiring centre / zone valves			**(see Note 3)**	1		
Sundries	@ 2.5 %						

Note 1	TV points to be run back to loft space. Left in postion ready for final connection along with main ariel installation by nominated TV engineer : not included in price.			
Note 2	If kitchen extract hood is required, installation and core cut to be carried out by kitchen fitter. Price quoted for is for supply and isolation only.			
Note 3	Central heating price has been based on a conventional S plan type system being specified. All second fix items to be supplied by nominated plumber / heating engineer.			

Materials quoted for :

- White goods :	Nexus BG range
- Consumer unit :	Hager
- Bathroom / Ensuite / porch light :	JCC Vinto JC8009WH (white)
- Recessed down lights (kitchen) :	Aurora AU-DLM981 (fire rated / mains voltage 50w halogen)
- Smoke dectector :	AICO Ei146

Sub - Total	£0
VAT @ 20%	£0
Total	£0

Terms & Conditions :	Please see attached document.

NICEIC DOMESTIC INSTALLER

TRUST MARK Government Endorsed Standards